



**SPECIFICATIONS FOR
TENDER #0171-1803
SUPPLY AND INSTALLATION OF
DIALYSIS PIPING MODIFICATION
WESTERN HEALTH**

Amendment 2 : Posted March 16th,2018

The following is being provided for clarification with regard to the work to be done:

1. Regarding asbestos abatement – there is drywall compound on the 3rd floor (Area below the Dialysis Department) which does contain asbestos. For any sections that are to be removed to conduct this work the Contractor is responsible for removing under Certified Abatement along with Air Testing.
2. Regarding Schedule of work – The schedule will have to be agreed upon before any work is started. It is estimated that the maximum beds to be shut down at one time will be 2. The work will have to be scheduled after regular hours. Portable equipment can be used for this install.
3. Hoarding – as per the hoarding plan, there may be times when there is a need to have access to multiple hoarding areas at a time. For example, Hoarding Area D and C would be needed simultaneously in order to complete that section of piping. Occupants would require relocation during this time. This will be approved with a schedule of when access is needed.
4. With regard to drain boxes – Surface mounted would be the best option to reduce the asbestos abatement work. We will accept options that provide proper functioning for the Dialysis unit.

CLOSING DATE: 20th of March, 2018

CLOSING TIME: 2:00 PM (Newfoundland Time)

—